





BARRICADES - FIRE HYDRANT AND OTHER

4" WIDE x 1/4" THICK
FLAT BAR. HORIZONTAL
BRACES MAY BE REQ'D.
BRACES TO BE SET ABOVE
HYDRANT OUTLETS
(INSTALL REFLECTORS
AS REQUIRED).

NTS



GENERAL NOTES:

1. FOR METER BOX MARKERS, THE MARKING SHALL BE "METER" AND THE HOUSE NO. ON THE BARRICADE IN SAME MANNER AS FOR VALVE MARKERS.
2. FOR VALVE MARKERS, THE LETTERS "VALVE" AND DISTANCE TO VALVE IN FEET SHALL BE WELDED OR BRAZED VERTICALLY ON BARRICADE IN 2 INCH HIGH LETTERS BEFORE PAINTING. LETTERS TO BE ON SIDE OF BARRICADE FACING VALVE.
3. SEE PLANS FOR NUMBER OF BARRICADES TO BE USED AND IF BRACES ARE REQUIRED.
4. THE EXACT LOCATION OF BARRICADES MAY BE CHANGED BY THE DISTRICT IN THE FIELD.
5. THE STEEL PIPE ABOVE GROUND SHALL BE PAINTED WITH 2 COATS OF DISTRICT APPROVED RED PRIMER.
6. FIRE HYDRANT BARRICADES SHALL BE PAINTED WITH 2 FINISH COATS OF DISTRICT APPROVED SAFETY YELLOW.
7. BARRICADES FOR FLUSHOUTS, AIR RELEASE VALVES, VAULT VENTS, AND MARKERS FOR VALVES AND METER BOXES SHALL BE PAINTED WITH 2 FINISH COATS OF DISTRICT APPROVED FOREST GREEN.

LOS ANGELES COUNTY WATERWORKS DISTRICTS

DEPARTMENT OF PUBLIC WORKS

STANDARD PLAN

W-14

APPROVED

ASSISTANT DEPUTY DIRECTOR

SEPTEMBER 2008

DATE

SHEET 1 OF 1