

WHITTIER BLDG. DIST. NO. 11

THE PLANS. HOUSE LATERAL, FROM CHIMNEYS SHALL NOT HAVE AN ANGLE OF LESS THAN 45° WITH THE MAIN LINE SEWER. ANY CHANGE IN ALIGNMENT SHALL BE REQUESTED IN WRITING BY THE PRIVATE ENGINEER.

S. NO REVISIONS SHALL BE MADE IN THESE PLANS WITHOUT THE APPROVAL OF THE COUNTY ENGINEER.

HOURS BEFORE STARTING ANY WORK UNDER THIS CONTRACT.

7. MANHOLES SHALL DE BRICK SEWER STRUCTURES PER S-3 . PRECAST CONCRETE MANHOLES PER S-5 OR S-6 MAY DE USED AS AN ALTERNATE IN LOCATIONS APPROVED BY THE COUNTY ENGINEER, EXCEPT AS MOTED.

8. USE STANDARD MANHOLE FRAMES AND COVERS, 5-15, EXCEPT AS NOTED.

9. MANHOLE TOPS IN UNIMPROVED RIGHTS-OF-WAY TO BE SIX INCHES ABOVE PINISHED GRADE.

10. USE EXTRA STRENGTH PIPE. ALL PIPE IS STANDARD DEPTH EXCEPT AS NOTED. MECHANICAL COMPRESSION JOINTS FOR ALL V.C.P. JOINTS PER SPEC'S., SECS. 36,44 \$49

UNLESS OTHERWISE APPROVED BY THE COUNTY ENGINEER

17. POR ALLOWABLE LEAKAGE TEST USE PORMULA NO 22 2 SPECS., SEC. S4.

18. ALL STATE AND LOCAL TRENCH SAFETY ORDERS WILL BE RIBIDLY ENFORCED.

PROFILE ALIGNMENT AND GRADE OF

TO BE CONSTRUCTED IN

SANITARY SEWERS

R/W N/O SANTA FE STREET

PRIVATE CONTRACT NO.7140

THOMSEN ENSINEERING INC.

GRADES TO WHICH THIS IMPROVEMENT IS TO BE CONSTRUCTED ARE SHOWN ON PLANS AND PROFILES. GRADE POINTS FOR TOP OF CURBS, CENTER LINE OF STREETS, OR CENTER LINE OF ALLEYS ARE SHOWN BY CIRCLES ON PROFILES. AT ALL POINTS BETWEEN DESIGNATED

POINTS THE GRADE SHALL BE ESTABLISHED SO AS TO CONFORM TO A STRAIGHT LINE DRAWN BETWEEN SAID DESIGNATED POINTS.

ELEVATIONS ARE IN FEET ABOVE U.S.C. & G.S. SEA LEVEL DATUM OF 1929.

THIS DRAWING AND THE DATA HEREON ARE HERBY MADE A PART OF THE SPECIFICATIONS,

WORK SHALL BE CONSTRUCTED ACCORDING TO STANDARD SPECIFICATIONS DATED BE MAY MOBE, ON PILE IN THE OFFICE OF THE

COUNTY ENGINEER AND SHALL BE PROSECUTED ONLY IN THE PRESENCE OF THE COUNTY ENGINEER.

BEFORE WORK CAN BE STARTED, THE CONTRACTOR MUST OBTAIN A PERMIT TO EXCAVATE IN COUNTY STREETS PROM THE L.A. COUNTY ROAD DEPT., DISTRICT OFFICE NO. AND PAY A FEE TO THE COUNTY ENGINEER, ROOM 330, COUNTY ENGINEERING BUILDING, 100 WEST SECOND STREET OR 405. CERRITORS.

CONSTRUCTION INSPECTION AND RECORD PLANS. APPROVAL OF THIS PLAN BY THE COUNTY OF LOS ANGELES DOES NOT CONSTITUTE A REPRESENTATION AS TO THE ACCURACY OF THE LOCATION OF OR THE EXISTENCE OR NON-EXISTENCE OF ANY UNDERGROUND UTILITY PIPE, OR STRUCTURE WITHIN THE LIMITS OF THIS

COUNTY OF LOS ANGELES, CALIFORNIA
BIE, COUNTY ENGINEER

J. D. PARKHURST, CHIEF ENGINEER


APPROVED BY, E. COTTEMBLE

SUBMITTED BY, John L. S. Klov 8-21-65
LOS CEGATOS REGIONAL ENCIPEER RED. C. 8. 40. 387/

(36802)

J. N.0364.23

COLLECT CHARGES AS INDICATED LELLINGWIN. OF OUT



NO CUNNECTIONS FOR THE DISPUSAL UN INDUSTRIAL WASTES SHALL BE MADE TO SEWERS SHOWN ON THESE DRAWINGS WITHOUT WRITTEN PERMISSION FROM THE CHIEF ENGINEER AND GENERAL MANAGER OF THE COUNTY SAMETATION DISTRICTS.

BEFORE BREAKING INTO ANY EXISTING STRUCTURE

BE NOTIFIED IN ORDER THAT REQUIRED INSPECTION CAN BE MADE.